टिप्पणी NOTES

कार्य का क्षेत्र SCOPE OF WORK	LUMDING-SILCHAR GAUGE CONVERSION PROJECT
केस सं. CASE NO.	
गेज GAUGE	B.G.
स्टेशन का वर्गक. STD. OF INTERLOCKING	III (R).
स्टेशन का वर्ग CLASS OF STATION	'B'
विचलन DEVIATION	AS LISTED
ड्रैफ्ट डिजाइन के अनुसार TO SUIT ENGG. PLAN NO.	CE/Y/23/2010 ALT-(I)
विगत डिजाइन का संदर्भ क्रम SUPERSEDES SIG. PLAN NO.	SG (SI) 4097

A) CRS's SPECIFIC APPROVAL TO BE OBTAINED IN TERMS OF PARA 3.40 (1) (b) OF G & SR OF N.F. RLY. 2004 EDITION FOR RECKONING THE ADEQUATE DISTANCE

a. AS 2UP/3UP FROM UP STARTER SIG. NO.–S14 TOWARDS DEAD END WHILE RECEIVING AN UP TRAIN ON LINE NO.–3 WHEN PTS. NO.103–104 NORMAL.

b. AS 1UP/3UP FROM UP STARTER SIG. NO.–S16 TOWARDS DEAD END WHILE RECEIVING AN UP TRAIN ON LINE NO.–1 WHEN PTS. NO.101–102 NORMAL.

c. AS 2UP/3UP FROM DN. STARTER SIG. NO.–S37 TOWARDS DEAD END WHILE RECEIVING A DN. TRAIN ON LINE NO.–3 WHEN PTS. NO.111–112 NORMAL.

d. AS 1UP/3UP FROM DN. STARTER SIG. NO.–S39 TOWARDS DEAD END WHILE RECEIVING A DN. TRAIN ON LINE NO.–1 WHEN PTS. NO.113–114 NORMAL.

B) CRS's SPECIFIC APPROVAL IS TO BE OBTAINED IN TERMS OF G.R. PARA 3.07(7) OF G & SR, 2004 EDITION OF N. F. RLY. FOR COMBINING :–

a. UP GATE DISTANT SIGNAL IN REAR OF UP GATE STOP SIGNAL NO. SII OF L.C. GATE NO. LK–10 WITH UP ADV. STARTER SIGNAL NO. S2.

b. DN. GATE DISTANT SIGNAL IN REAR OF DN. GATE STOP SIGNAL NO. SII OF L.C. GATE NO. LK–11 WITH DN. ADV. STARTER SIGNAL NO. S47.

c. UP DISTANCE SIGNAL IN REAR OF UP MAIN HOME SIGNAL NO.–S46 WITH THE UP GATE STOP SIGNAL NO. SIV OF L.C. GATE NO. LK–11.

d. DN. DISTANCE SIGNAL IN REAR OF DN. MAIN HOME SIGNAL NO.–S3 WITH THE DN. GATE STOP SIGNAL NO. SI OF L.C. GATE NO. LK–10.